



S4 / 3/8"=1'-0"


- KEY NOTES -

- 1 3 1/2"x3 1/2"x1/4" HSS
- 2 FLOOR BEAM PER SCHEDULE BELOW
- 3 LONGITUDINAL ROOF CHANNEL PER 5/S3.1
- 4 12 GA. TRANSVERSE ROOF CHANNEL PER 6/S3.1
- 6" Ø MAX OPENING IN WEB OF ROOF BEAM WITHOUT WEB REINFORCEMENT PER 5/S4 MINIMUM SPACING OF HOLES @ 48" O.C. HOLES MAY OCCUR @ ANY LOCATION ALONG LENGTH OF ROOF BEAM EXCEPT AS NOTED OTHERWISE ON FRAMING ELEVATION NOTE: IF HOLE IS 3" OR LESS THEY MAY BE SPACED AT 24" O.C. MINIMUM
- 4" Ø MAX OPENING IN WEB OF FLOOR BEAM WITHOUT WEB REINFORCEMENT PER 6/S4 MINIMUM SPACING OF HOLES @ 48" O.C. HOLES MAY OCCUR @ ANY LOCATION ALONG LENGTH OF FLOOR BEAM WITH DIRECT FOUNDATION SUPPORT BELOW. OPENINGS ARE NOT ALLOWED WHERE BEAMS ARE SPANNING BETWEEN FOUNDATIONS OR ACROSS VENT OPENINGS.
- NOTE: IF HOLE IS 2" OR LESS THEY MAY BE SPACED AT 24" MINIMUM
- 7 14 GA OUTRIGGER CHANNEL AT ENCLOSED OVERHANG REFER TO DETAIL 1/S4
- 8 OPENING FOR HVAC UNIT

SUBFLOOR TYPE	FLOOR BEAM SIZE	ALTERNATES
VIROC OR PLYWOOD	C7×9.8	C9x13.4, C10x15.3
CONCRETE	C9x13.4	C10x15.3







THE WELDING PROCEDURE QUALIFICATION TEST RECORD AND WELDING PRODECURE SPECIFICATION FOR THIS WELD SHALL BE PREPARED IN ACCORDANCE WITH AWS D.1-06 AND SUBMITTED TO THE STRUCTURAL

REVISIONS			
NO	DATE	DESCRIPTION	
A			
2			
3	-		
4			

DATE:
SCALE: NOTED
DRAWN BY: RL
SERIAL NO.:

CUSTOMER:

2 1/2:12 PITCHED ROOF 30' x 32' THRU 120' x 32' RELOCATABLE BUILDINGS

TYPICAL FRAME ELEVATIONS

American Modular Systems Inc.
787 Spreckels Ave. Manteca, CA 95336
(209)825-1921 Fax (209)825-7018
american modular.com

