1 PARTIAL SITE ELECTRICAL DEMOLITION PLAN SCALE: 1/16"=1'-0"

**DEMOLITION NOTES** 


- 1. SCOPE: PROVIDE AND PERFORM DEMOLITION, PREPARATORY AND MISCELLANEOUS WORK IN AREAS AS INDICATED AND SPECIFIED, COMPLETE.
- 2. DEMOLITION AND REMOVAL OF EXISTING ELECTRICAL CONDUIT, WIRING AND EQUIPMENT REQUIRED TO COMPLETE THE PROJECT.
- 3. PREPARATION OF THE EXISTING BUILDING TO RECEIVE OR CONNECT THE NEW WORK.
- 4. MISCELLANEOUS DEMOLITION, CUTTING, ALTERATION, AND REPAIR WORK ON EXISTING SITE AND IN THE EXISTING BUILDING NECESSARY FOR THE COMPLETION OF THE ENTIRE PROJECT.
- 5. DISCONNECTING AND RECONNECTION OF ELECTRICAL EQUIPMENT AS REQUIRED BY THE CONSTRUCTION MODIFICATIONS.
- 6. EXISTING CONDITIONS: PRIOR TO BID MAKE A DETAILED SURVEY OF THE EXISTING CONDITIONS PERTAINING TO THE WORK. CHECK THE LOCATIONS OF ALL EXISTING STRUCTURES, EQUIPMENT AND WIRING (BRANCH CIRCUITING AND CONTROLS). CHECK FOR ANY HAZARDOUS MATERIALS WHICH MAY REQUIRE SPECIAL HANDLING.
- 7. SALVAGE AND DISPOSAL: ALL REMOVED MATERIAL, OTHER THAN ITEMS TO BE REUSED, SHALL BE RETURNED TO THE OWNER OR DISPOSED OF IN ACCORDANCE WITH INSTRUCTIONS FROM THE OWNER'S REPRESENTATIVE. DISPOSAL SHALL BE DONE IN ACCORDANCE WITH EPA AND GOVERNING BODY REQUIREMENTS AND REGULATIONS. CONTRACTOR SHALL PAY FEES AND CHARGES FOR DISPOSAL.
- 8. TWO WEEKS PRIOR TO THE START OF ANY WORK, CONTRACTOR SHALL SCHEDULE ALL WORK AND ELECTRICAL SYSTEM OUTAGES WITH OWNER'S WRITTEN APPROVAL.
- 9. PROTECT ALL EXISTING POWER, MOTORS AND RELATED EQUIPMENT, ALARM SYSTEM, LIGHTING AND CONTROL SYSTEMS, AND TELEPHONE EQUIPMENT IN PLACE, UNLESS OTHERWISE NOTED.
- 10. CONTRACTOR SHALL LEAVE ALL POWER AND SIGNAL CIRCUITS ENRGIZED, VIA JUNCTION BOX, TO DEVICES IN AREAS OUTSIDE OF DEMOLITION AREA EVEN IF SYSTEMS ARE ROUTED THROUGH DEMOLITION AREA.

LITION, ORK IN AREAS TE. San Luis Obispo

San Luis Obispo 4119 Broad Street, Suite 210 San Luis Obispo, CA 93401 805.546.0433 fax: 805.546.0504 ibigroup.com

SEAL

PRIME CONSULTANT



COPYRIGHT:
Any reproduction or distribution for any purpose other than authorized by IBI Group is forbidden.

COPYRIGHT 2017 IBI GROUP


REVISIONS

NO. DATE APPRD. DESCRIPTION

CONSULTANT

## FERRANTI ENGINEERING

CONSULTING
ELECTRICAL ENGINEERS
1211 MARICOPA HWY,
SUITE 250
OJAI, CA 93023
(805) 705-4772
DALEFERRANTI@LIVE.COM



ISTRUC.

NO

AGENCY INFORMATION:

AGENCY TRACKING NO. 63321-241

identification stamp DIV. OF THE STATE ARCHITECT OFFICE OF REGULATION SERVICES

0 3 - 1 1 8 3 8 0

AC FLS SS CU DATE OCT 2 5 2017

BAKERSFIELD CITY SCHOOL DISTRICT



BESSIE OWENS INTERMEDIATE RELOCATABLES A101 - A106

815 EUREKA ST. BAKERSFIELD CA, 93305

OPSC or OSHPD PROJ. NO:
PROJECT NO: 16241.000

DRAWN BY: VZ

CHK'D BY: DF

ISSUE DATE: 8/2

SHEET TITLE

PARTIAL SITE ELECTRICAL DEMOLITION PLAN

SHEET NUMBER

E1.4

