


KEY NOTES


- AC1. WALL MOUNT 3.5 TON HEAT PUMP NOMINAL 47,000 BTUH COOL / 46,000 BTUH HEAT W/5kw HEATER OLA AND CALIFORNIA STATE ENERGY APPROVED 208 / 230V, 1 PHASE, MAX FLA 28 AMPS WEIGHT 510 LBS.
- THERMOSTAT-WHITE ROGERS 1F92+48 A.F.F.
- 3 12" FLEX DUCT
  - - SUPPLY AIR GRILLE
- 5 10" X 30" X 2' PLENUM (SEE SPECS)

## NOTES

- INSULATION APPLIED TO EXTERIOR SURFACE OF DUCTS LOCATED IN BLDGS SHALL HAVE A FLAME SPREAD OF NOT MORE THAN 25 & A SMOKE-DENSITY NOT EXCEEDING 50 WHEN TESTED AS A COMPOSITE INSTALLATION INCLUDING INSULATION, FACING MATERIALS, TAPES & ADHESIVES AS NORMALLY APPLIED EXCEPTION: INSULATION HAVING A FLAME PREAD MOEX NOT EXCEEDING SO & A SMOKE DENSITY NOT ORESTER THAN 100 MAY BE INSTALLED IN DWELLINGS OR APARTMENT HOUSES WHERE THE DUCT SYSTEM SERVES NOT MORE THAN ONE DWELLING UNIT.
- SCHOOL EQUIPMENT ANCHORAGE
- THE FOLLOWING IS FOR THE MECHANICAL ENGINEER'S INFORMATION ONLY
- THE SEISMIC ANCHORAGE OF MECHANICAL EQUIPMENT SHALL CONFORM
  TO C C R TITLE 24, SECTION 12/30/2/2 AND TABLE 12-AID ANCHORAGE DETAILS
  FOR ROOF/FLOOR MOUNTED EQUIPMENT WEIGHING LESS THAN 400 LBS AND HUNG
  EQUIPMENT WEIGHING LESS THAN 20 LBS MAY BE OMITTED FROM THE PLANS FOR MECHANICAL DRAWINGS:
- ALL MECHANICAL EQUIPMENT SHALL BE BRACED OR ANCHORED TO RESIST A HORIZONTAL FORCE ACTING IN ANY DIRECTION USING THE FOLLOWING CRITERIA
- EQUIPMENT ON GRADE 20% OF OPERATING WEIGHT 30% OF OPERATING WEIGHT
- FOR FLEXIBLY MOUNTED EQUIPMENT USE 4 X THE ABOVE VALUES, AND FOR SIMULTANEOUS VERTICAL FORCE USE 1/3 X THE HORIZONTAL FORCE
- THE ABOVE VALUES ARE FOR AN IMPORTANCE FACTOR, I=10 AND SEISMIC ZONE , Z=0.4

WHERE ANCHORAGE DETAILS ARE NOT SHOWN ON THE DIMININGS THE FIELD INSTALLATION SHALL BE SUBJECT TO THE APPROVAL OF THE MECHANICAL ENG. AND THE FIELD ENGINEER OF THE OFFICE OF THE STATE ARCHITECT






MECHANICAL PLAN (24' X 40')


SCALE 1/4"=1'-0"


APP#3 117 168

REVISED Structural Engineer's Seal techenical Engineer's Seat

REVISIONS







MODTECH INC.

2830 BARRETT AVENUE PERRIS, CALIF. 92572 PH (909) 943-4014 FAX (909) 940-0427 PROJECT NUMBER:

2986

MODTECH, INC.

checked by 05 JAN 99

MODIFICAL INSER NO M1.0

MECHANICAL (HVAC) PLAN