FINISH SCHEDULE

MUNSEY SCHOOL MODERNIZATION

UNIT	RM. #	ROOM NAME	BASE (E)	BASE (N)	FLOOR (E)	FLOOR (N)	WALLS NORTH MAT	WALLS NORTH FIN	WALLS SOUTH MAT	WALLS SOUTH FIN	WALLS EAST MAT	WALLS EAST FIN	WALLS WEST MAT	WALLS WEST FIN	WAINSCOT NORTH MAT	WAINSCOT NORTH FIN	WAINSCOT SOUTH MAT	WAINSCOT SOUTH FIN	WAINSCOT EAST MAT	WAINSCOT EAST FIN	WAINSCOT WEST MAT	WAINSCOT WEST FIN	CEILINGS (E)	CEILINGS (N)	CEILINGS (E) HT.	CEILINGS (N) HT.	DOORS	SASH	REMARKS
E	5	JANITOR	A	W	F	W	M	W	M	W	M	W	M	W	--	--	--	--	--	--	--	--	A1 M	W					
E	6	CLASSROOM	B	D W	G	J	K	L	K	L	K	L	K	L	--	--	--	--	--	--	--	--	A1 M	P		9'-8"			
E	7	CLASSROOM	B	D W	G	J	K	L	K	L	K	L	K	L	--	--	--	--	--	--	--	--	A1 N	P		9'-8"			
E	8	BOY'S TOILET	H	D W	H	L	M	L	M	L	M	L	M	L	H	D W	H	D W	H	D W	H	D W	A1 M	L					
E	9	GIRL'S TOILET	H	D W	H	L	M	L	M	L	M	L	M	L	H	D W	H	D W	H	D W	H	D W	A1 M	L					
E	10	STORAGE	-	-	F	W	M	W	M	W	M	W	M	W	--	--	--	--	--	--	--	--	A1 M	W					
E	11	STORAGE	B	W	G	W	M	W	M	W	M	W	M	W	--	--	--	--	--	--	--	--	A1 M	W					
E	12	ARCADE	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	A1	—					
R1	1	CLASSROOM	B	D	A1		M	L	M	L	M	L	M	L	--	--	--	--	--	--	--	--	A1 N	P		9'-8"			
R2	1	LIBRARY	B	D	A1		M	L	M	L	M	L	M	L	--	--	--	--	--	--	--	--	A1 N	P		9'-8"			
R5	1	CLASSROOM	B	D	A1		M	L	M	L	M	L	M	L	--	--	--	--	--	--	--	--	A1 N	P	10'-1"	8'-0"			
R5	2	CLASSROOM	B	D	A1		M	L	M	L	M	L	M	L	--	--	--	--	--	--	--	--	A1 N	P	10'-1"	8'-0"			
R5	3	CLASSROOM	B	D	A1		M	L	M	L	M	L	M	L	--	--	--	--	--	--	--	--	A1 N	P	10'-1"	8'-0"			
R5	4	CLASSROOM	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--			
R5	5	CLASSROOM	--	--	--	--	--	--	--	A1	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--			

KEY NOTES 8712 FIN KEY

NOTES LISTED IN THIS COLUMN WHICH ARE NOT INDICATED ON THIS SHEET SHALL BE DISREGARDED. COMPLETE PATCH AND REPAIR OF AREAS AND ADJACENT AREAS WHERE REMOVAL, DEMOLITION OR MODIFICATIONS ARE MADE ARE A PART OF THIS WORK. FIELD VERIFICATION FOR ACTUAL EXISTING CONDITIONS PRIOR TO BIDDING, FABRICATION, INSTALLATION OR CONSTRUCTION IS A PART OF THIS WORK. NOTES ARE TYPICAL UNLESS OTHERWISE INDICATED.

LEGEND

(N) = NEW;
(E) = EXISTING;
(D) = DEMOLITION;

AS SDSS = AS SHOWN, DETAILED, SCHEDULED, &/OR SPECIFIED.

A. (E) CONCRETE BASE.
B. (E) WOOD BASE.
C. (E) CERAMIC TILE BASE.
D. (N) 4" RUBBER TOP SET BASE.
E. (N) 4" RUBBER TOP SET BASE AT (N) CABINETS.
F. (E) CONCRETE FLOOR.
G. (E) ASPHALT TILE.
H. (E) CERAMIC TILE.
J. (N) CARPET.
K. (E) PLYWOOD PANEL.
L. (N) PAINT.
M. (E) PLASTER.
N. (E) ACOUSTIC TILE.
P. (N) SUSPENDED T-BAR W/ACOUSTIC PANELS.
Q. FACTORY FINISH.
R. (E) CARPET.
S. (E) SUSPENDED T-BAR W/ACOUSTIC PANELS.
T. (E) EXPOSED RAFTERS.
U. (E) 1/8" MASONITE (PERFORATED).
V. (E) 5/8" GYP-SUM WALLBOARD.
W. (E) TO REMAIN.
Y. (E) TO BE REMOVED.
Z. (E) SURFACE PREPARE FOR (N) CARPET OR (N) VINYL COMPOSITION TILE.
A1. (E) CLEAN & REPAINT WHERE LEFT EXPOSED.
B1. (E) SAND & REFINISH
C1. (E) CEILING TO REMAIN.
D1. (N) CERAMIC TILE @ DEMO
E1. (N) VINYL TILE FLOORING.

TITLE 24 & 1979 UBC

5241 Rm/LM

date
6/23/89
revisions

MUNSEY SCHOOL MODERNIZATION
BAKERSFIELD CITY SCHOOL DISTRICT
BAKERSFIELD, CALIFORNIA

APPROVED
Department of State Architect
Structural Safety

Kendrick Design Group
Glen Kendrick AIA
architects • planners
2115 9th street • bakersfield, ca 93301 • (805) 322-1863

job number
8712

sheet number
A•21